

Report 11528
22 July 1999

Integrated Advanced Microwave Sounding Unit-A
(AMSU-A)
Performance Verification Report
Antenna Drive Subsystem
METSAT AMSU-A2 (PN: 1331200-2, SN: 109)

GENCORP
AEROJET

Contract No. NAS 5-32314
CDRL 208

Submitted to:

National Aeronautics and Space Administration
Goddard Space Flight Center
Greenbelt, Maryland 20771

Submitted by:

Aerojet
1100 West Hollyvale Street
Azusa, California 91702

Aerojet

**Report 11528
22 July 1999**

**Integrated Advanced Microwave Sounding Unit-A
(AMSU-A)
Performance Verification Report
Antenna Drive Subsystem
METSAT AMSU-A2 (PN: 1331200-2, SN: 109)**

**Contract No. NAS 5-32314
CDRL 208**

Submitted to:

**National Aeronautics and Space Administration
Goddard Space Flight Center
Greenbelt, Maryland 20771**

Submitted by:

**Aerojet
1100 West Hollyvale Street
Azusa, California 91702**

AMSU-A VERIFICATION TEST REPORT

TEST ITEM:	METSAT AMSU- A2 ANTENNA DRIVE SUBSYSTEM PART OF P/N: 1331200-2 SERIAL NUMBER: 109
LEVEL OF ASSEMBLY:	SUBASSEMBLY AND COMPLETE INSTRUMENT ASSEMBLY
TYPE HARDWARE:	FLIGHT
PROCEDURE NO:	AE-26002/2E
TEST COMPLETION DATE:	6 JUNE 1999

TABLE OF CONTENTS

1.0	INTRODUCTION
2.0	SUMMARY
3.0	TEST CONFIGURATION - SUBASSEMBLIES
4.0	TEST CONFIGURATION - SUBSYSTEM
5.0	TEST RESULTS
5.1	DRIVE AND COMPENSATOR ASSEMBLIES
5.2	CIRCUIT CARD ASSEMBLIES (CCAs)
5.3	SIGNAL PROCESSOR
5.4	TRANSISTOR ASSEMBLY
5.5	ANTENNA DRIVE SUBSYSTEM TESTS
5.5.1	SCAN MOTION AND JITTER
5.5.2	28V BUS PEAK CURRENT AND RISE TIME
5.5.3	RESOLVER READING AND POSITION ERROR
5.5.4	GAIN AND PHASE MARGIN
5.5.5	OPERATIONAL GAIN MARGIN
6.0	CONCLUSION
7.0	TEST DATA


1.0 INTRODUCTION

The antenna drive subsystem test was performed on the METSAT AMSU-A2 S/N 109 (P/N 1331200-2) instrument. The objective of the test was to demonstrate compliance with applicable paragraphs of AMSU-A specification S-480-80 when tested using AE-26002/2E. Tests were conducted at both the subassembly and subsystem (instrument) level.

2.0 SUMMARY

The performance verification tests include 1) scan motion and jitter, 2) pulse load bus peak current and risetime, 3) resolver reading and position error, 4) gain and phase margin and 5) operational gain margin.

Subassembly tests are performed on the drive assembly, compensator assembly, circuit card assemblies (CCAs), signal processor and the transistor assembly. The transistor assembly was tested during the W3 cable assembly (1356946-1) test. Refer to Figure 1 for test flow.



Antenna Subsystem and Subsystem Component Test Flow
Figure 1.

The antenna drive subsystem satisfactorily passed all tests to verify the performance requirements. There were no failures in any of the antenna drive components during subsystem testing. There were several anomalies during subassembly testing. Refer to paragraph 5.0 for a discussion of test results.

3.0 TEST CONFIGURATION – SUBASSEMBLIES

Subassemblies are tested using a variety of test fixtures as required to perform the necessary tests.

Drive Assembly – Prior to complete buildup of this assembly, a starting torque test is performed on the rotating part of the assembly. The test is performed at temperatures of 23, 4, and -10°C . The tests performed on the completed assembly are 1) motor commutation, 2) resolver operation and no-load speed, 3) temperature sensor resistance and output voltage and 4) random vibration. Motor commutation and resolver operation and no-load speed are repeated after vibration.

Compensator Assembly – The tests performed on this assembly are 1) motor commutation, 2) temperature sensor resistance and output voltage and 3) random vibration. Motor commutation is repeated after vibration.

CCAs – All CCAs are tested prior to being incorporated into the signal processor. They are tested to verify functionality and the derived performance requirements.

Signal Processor – Part of the signal processor test is associated with the antenna drive subsystem. The test includes all applicable CCAs installed in the signal processor card cage, the STE with the associated cabling to the signal processor, and a test motor and inertia wheel to simulate the antenna drive motor and reflector load. This test demonstrates that all signal processor scan drive circuitry is functioning as a subsystem prior to assembly into the instrument. During the tests, qualitative reflector position for the various scan modes is verified by visually observing an index mark on the inertia wheel.

Transistor Assembly – The W3 cable is first tested on the CKT 1000 (continuity and hi-pot tester). The transistor assembly is then mated with the W3 cable, and tested using a special test fixture. The test assures that the transistors saturate when turned on, and that they turn off.

4.0 TEST CONFIGURATION – SUBSYSTEM

The antenna drive subsystem tests are performed after all of the scan drive subassemblies are assembled into the instrument, and the subsystem is tested in accordance with AE-26002/2 during system integration. At the beginning of system integration testing, the instrument is first proven electrically safe by ground isolation and power distribution checks. The instrument is supplied with 28 Vdc from the STE, and the DC-DC converter is installed to supply the other required voltages to the CCAs.

The tests performed to verify performance are 1) scan motion and jitter, 2) pulse load bus peak current and risetime, 3) resolver reading and position error, 4) gain and phase margin and 5) operational gain margin. In order to verify scan motion and jitter, it is necessary to obtain real time measurement of the drive assembly shaft position. This is done by using a continuous rotation potentiometer (pot) mechanically coupled to the drive assembly shaft, and connecting a source of dc voltage across the pot. The voltage at the pot wiper then gives a voltage analog of shaft position for each revolution of the shaft.

Prior to the performance verification tests, there are five operations performed. These are described as follows:

1. An EPROM is programmed with the reflector position commands (14-bit digital words) which are calculated from the nadir position obtained on the antenna range. This PROM is one of the components on the memory board in the signal processor, and it is under microprocessor control for positioning the reflector. Reprogramming may be necessary if the measured reflector positions are not within the specified limits. (See 5.5.3).
2. After obtaining the PROM, the instrument is powered, and scan motion is qualitatively checked to conform to the pattern as shown in Appendix B1.
3. The motor (drive and compensator) current limits are set with select at test (SAT) resistors.
4. The individual steps in the scan are tailored for risetime, overshoot and jitter with SAT resistors which are part of circuits in the rate loop.
5. The mechanical resonant frequencies of the drive assembly and reflector are identified. They are then nullified by selecting the appropriate frequencies for three notch filters.

The antenna drive subsystem subassemblies designated for use in the METSAT AMSU-A2 S/N 109 instrument are shown in Table 1.

CCAs	S/N
Resolver Data Isolator	F24
Interface Converter	F24
Motor Driver 3-Hall Sensor	F07
Motor Driver 3-Hall Sensor	F08
R/D Converter/Oscillator	F12

OTHER	S/N
Antenna Drive Assembly	F08
Compensator Assembly	F09
Signal Processor	F05
Transistor Assembly (W3 Cable)	NONE

Table 1. A2 109 Subassembly S/N

5.0 TEST RESULTS

The test results for the subassemblies are first presented in paragraphs 5.1 through 5.4. The subsystem test results are presented in 5.5.

5.1 DRIVE AND COMPENSATOR ASSEMBLIES

When the F08 drive assembly was vibrated, it was found to have natural frequencies about 13 % lower than the average tested drive assembly (TAR 005089). Investigation revealed no anomaly and the TAR was closed.

Also on the drive assembly, a clicking noise was heard when the motor commutation was run (TAR 002684). Excessive slack in one wire in a wire bundle caused the wire to contact the rotating assembly. A spot tie was removed, the slack was taken out and the tie was redone.

When the temperature sensor output voltage on the compensator assembly was measured, it was found to be out of limits (TAR 002750). Troubleshooting revealed a miswiring. After rework, the output voltage was within limits.

5.2 CCAs

There were no test anomalies or failures during testing of the CCAs for this instrument. The test data sheets (TDSs) for the CCAs are presented in Appendices A1 through A4.

5.3 SIGNAL PROCESSOR

There were no test anomalies or failures during the scan drive part of the testing of the signal processor for this instrument.

5.4 TRANSISTOR ASSEMBLY

There were no test anomalies or failures during testing of the transistor assembly for this instrument.

5.5 ANTENNA SUBSYSTEM

There were no test anomalies or failures during testing of the antenna drive subsystem for this instrument. A discussion of test results is given in paragraphs 5.5.1 through 5.5.5.

5.5.1 SCAN MOTION AND JITTER

In this test, the antenna position is measured in a series of five full scans. The measurement was made with the continuous rotation test pot temporarily affixed to the motor shaft. A Dynamic Signal Analyzer (DSA) is connected to the pot wiper to record the antenna position. Five scans were captured and stored on the AMSU-A2 Test Data File disc. One representative pattern is presented in Appendix B1.

Each 3.33 degree scene step was expanded in order to verify risetime, overshoot and jitter. The risetime limit is 42 ms, the jitter limits are $\pm 5\%$ and the overshoot limit is 4 % above the upper jitter limit. The expanded waveforms were plotted and are presented in Appendices B2 through B30. All of the scene steps meet the step response requirements.

Slew periods to the cold and warm calibration stations were measured and met requirements. A time of 0.21 s is allowed for the 35 degree slew to cold cal, and 0.4 s for the 96.67 degree slew to warm cal. Calibration station jitter is less than the $\pm 5\%$ maximum allowed. Expanded waveforms were plotted and are presented in Appendices B31 and B32. The waveforms are also stored on the AMSU-A2 Test Data File disc. The test data sheet is presented in Appendix B33.

5.5.2 PULSE LOAD BUS PEAK CURRENT AND RISE TIME

The peak current must be less than 2 A at any beam position along the scan, and it was measured to be 1.997 A. The current risetime while transitioning from one beam position to the next, and the risetime at the start and stop of the slew to warm cal position must be greater than 70 μ s. One 3.33° step was selected, and the risetime is 2.344 ms. For the slew to warm cal, the times are 3.906 ms and 1.953 ms for start and stop respectively.

The full scan pulse load bus current waveform is presented in Appendix C1, and the TDS is presented in Appendix C2. The waveform is also stored on the AMSU-A2 Test Data File disc.

5.5.3 RESOLVER READING AND POSITION ERROR

Reflector positions are obtained by using the STE, which displays the resolver readings to be compared with the position commands. Two readings are taken, one at the start of integration (LOOK 1), and the other halfway into the integration period (LOOK 2). The limits on the difference between the reported position (actual) and the command are ± 10 counts for LOOK 1 and ± 5 counts for LOOK 2. A table of reflector position commands and the reported position obtained from the STE computer printout is shown in Table 2, together with the differences between actual and command.

BP	Command	Actual		Difference*		BP	Command	Actual		Difference*	
		Look 1	Look 2	Look 1	Look 2			Look 1	Look 2	Look 1	Look 2
1	5595	5954	5954	-1	-1	19	3225	3226	3224	1	-1
2	5803	5807	5804	4	1	20	3073	3073	3073	0	0
3	5651	5655	5652	4	1	21	2921	2923	2920	2	-1
4	5500	5504	5501	4	1	22	2770	2771	2770	1	0
5	5348	5352	5349	4	1	23	2618	2619	2618	1	0
6	5196	5200	5197	4	1	24	2466	2467	2466	1	0
7	5045	5048	5046	3	1	25	2315	2317	2315	2	0
8	4893	4896	4894	3	1	26	2163	2163	2163	0	0
9	4741	4746	4742	5	1	27	2010	2013	2011	3	1
10	4590	4594	4591	4	1	28	1860	1861	1860	1	0
11	4438	4441	4440	3	2	29	1708	1708	1708	0	0
12	4286	4289	4287	3	1	30	1556	1558	1556	2	0
13	4135	4137	4135	2	0	WC	11948	11948	11949	0	1
14	3983	3984	3983	1	0	CC1	16347	16346	16347	-1	0
15	3830	3833	3831	3	1	CC2	38	40	40	2	2
16	3680	3682	3680	2	0	CC3	115	117	117	2	2
17	3528	3529	3528	1	0	CC4	266	268	268	2	2
18	3376	3378	3375	3	-1						

BP = Beam position

*Actual - Command

Table 2. Reflector (Beam) Position Commands and Measurements

5.5.4 GAIN AND PHASE MARGIN

The gain and phase margin test is performed on the position control loop of the antenna drive subsystem. Three separate open loop gain and phase plots (measured with the loop closed) are obtained. The DSA is used to make the plots using the swept sine mode. Gain margin is measured at the -180° phase crossover frequency, and phase margin is measured at the 0 dB gain crossover frequency. The margins on each of the three plots are above the minimum specification requirement of 12 dB and 25 degrees for the gain and phase respectively. The plots are presented in Appendices D1 through D3, and the TDS is presented in Appendix D4. The plots are also stored on the AMSU-A2 Test Data File disc.

5.5.5 OPERATIONAL GAIN MARGIN

The operational gain margin test is also done three times. This test consists of increasing the gain inside the rate loop until oscillation occurs. The gain increase is calculated and the frequency of oscillation is measured from the spectrum plot using the DSA. An increase in gain greater than 9 dB is required, and the frequency of oscillation is just recorded.

To increase the gain, a 50 k Ω pot is connected in series with the R58 feedback resistor on amplifier AR8 on the R/D Converter/Oscillator CCA. The resistance of the test pot is slowly added to the feedback resistor while observing the reflector for oscillations. The reflector begins to produce an audible sound as gain is increased to the point of oscillation. Table 3 shows the added resistance values and the calculated gain margin.

Resistance (k Ω)	Gain Margin (dB)
38.58	9.3
41.20	9.7
42.88	9.9

Table 3. Pot Resistance and Operational Gain Margin

The first mode mechanical resonance of the shaft and reflector is about 228 Hz as shown in the power spectrum. The spectrum was plotted and is presented in Appendix E1, and the TDS is presented in Appendix E2. The spectrum plot is also stored on the AMSU-A2 Test Data File disc.

6.0 CONCLUSION

Based on the test results, it can be concluded that the METSAT AMSU-A2 S/N 109 antenna drive subsystem meets the AMSU-A specification requirements.

7.0 TEST DATA

Test data for the CCAs and the antenna drive subsystem is presented in the appendices as outlined in the Appendix Index on the following page.

APPENDIX INDEX

<i>Appendix A1</i>	<i>Resolver Data Isolator CCA TDS</i>
<i>Appendix A2</i>	<i>Interface Converter CCA TDS</i>
<i>Appendix A3</i>	<i>Motor Driver 3-Hall Sensor CCA TDS</i>
<i>Appendix A4</i>	<i>R/D Converter/ Oscillator CCA TDS</i>
<i>Appendix B1</i>	<i>Full Scan Step Response</i>
<i>Appendix B2 thru B30</i>	<i>Single Step Responses</i>
<i>Appendix B31</i>	<i>Cold Calibration Step Response</i>
<i>Appendix B32</i>	<i>Warm Calibration Step Response</i>
<i>Appendix B33</i>	<i>Scan Motion and Jitter TDS</i>
<i>Appendix C1</i>	<i>Peak Pulse Load Bus Current Waveform</i>
<i>Appendix C2</i>	<i>Pulse Load Bus Current TDS</i>
<i>Appendix D1 thru D3</i>	<i>Gain and Phase Margin Plots</i>
<i>Appendix D4</i>	<i>Gain and Phase Margin TDS</i>
<i>Appendix E1</i>	<i>Operational Gain Margin Power Spectrum</i>
<i>Appendix E2</i>	<i>Operational Gain Margin TDS</i>

TEST DATA SHEET B-6 (Sheet 1 of 2)

RESOLVER DATA ISOLATOR CCA (P/N 1334972) (Paragraph 6.6.7)

Date: 4/14/97
S/N: F-24
1334972-1

6.6.7.1 Supply Voltages

Supply*	Measured Value (V)	Limits (Vdc)	Pass/Fail
+5 V (I)	5.01	± 0.25	P
+5 V (U)	5.00	± 0.25	P

6.6.7.2 Supply Currents

Steps 1 and 2:

Supply*	Measured Value (mA)	Limits (mA)	Pass/Fail
+5 V (I)	53.38	100 max	P
+5 V (U)	333.00	400 max	P

1000
4-16-97

Steps 3 and 4:

Supply*	Measured Value (mA)	Limits (mA)	Pass/Fail
+5 V (I)	83.60	150 max	P
+5 V (U)	11.06	30 max	P

* I = Isolated, U = Unisolated

6.6.7.3 Resolver Data

Bit No.	Pass/Fail
API 0 - AP Bit 0	P
API 1 - AP Bit 1	P
API 2 - AP Bit 2	P
API 3 - AP Bit 3	P
API 4 - AP Bit 4	P
API 5 - AP Bit 5	P
API 6 - AP Bit 6	P
API 7 - AP Bit 7	P
API 8 - AP Bit 8	P
API 9 - AP Bit 9	P
API 10 - AP Bit 10	P
API 11 - AP Bit 11	P
API 12 - AP Bit 12	P
API 13 - AP Bit 13	P

6.6.7.4 Converter Busy Pulse

Converter Busy Pulse	Measured Value (µsec)	Limits (µsec)	Pass/Fail
15.0	14.75	± 3.0	P

TEST DATA SHEET B-6 (Sheet 2 of 2)

RESOLVER DATA ISOLATOR CCA (P/N 1334972) (Paragraph 6.6.7)

Comments:

NONE

Conducted by:

[Signature]
Test Engineer

4/14/97

Date

Verified by:

[Signature]
Quality Control Inspector

4-16-97

Date

Approved by:

[Signature]
DCMC

4/16/97

Date

TEST DATA SHEET B-13 (Sheet 1 of 3)

INTERFACE/CONVERTER CCA (P/N 1331697) (Paragraph 6.13.7)

Date: 8/5/97
CCA S/N: F24
1331697-1

6.13.7.1 Supply Voltages

Supply	Measured Value (Vdc)	Limits (Vdc)	Pass/Fail
+5V (U)	5.00	+5V±0.05	P
+15V (I)	15.01	+15V±0.15	P
-15V (I)	-14.98	-15V±0.15	P
+5V (I)	5.02	+5V±0.05	P

6.13.7.2 Supply Currents

Step 1 (CP and API Low):

Supply	Measured Value (mA)	Limits (mA)	Pass/Fail
+5V (U)	86.55	70 - 110	P
+5V (I)	3.38	1.5 - 5.5	P
+15V (I)	17.76	15 - 23	P
-15V (I)	20.46	18 - 26	P

Step 2 (CP and API High):

Supply	Measured Value (mA)	Limits (mA)	Pass/Fail
+5V (U)	86.58	40 - 70	P
+5V (I)	23.96	18 - 30	P
+15V (I)	17.76	15 - 23	P
-15V (I)	20.46	18 - 26	P

6.13.7.3 Amplifier Offsets

Amplifier	Measured Value (mV)	Limits (mV)	Pass/Fail
AR1	-0.07	0.0±0.15	P
AR2	-0.20	0.0±2.0	P

19 Jun 97

TEST DATA SHEET B-13 (Sheet 2 of 3)

INTERFACE/CONVERTER CCA (P/N 1331697) (Paragraph 6.13.7)

6.13.7.4 Subtraction and D-A Conversion

Step 1:

unturned
9-10-97
 ± 0.00015
 ± 0.00060
 ± 0.00030

Actual Position (API) MSB LSB	Command Position (CP) MSB LSB	ARI Output Voltage Required (Vdc)	Test Result (Vdc)	Pass/Fail
00000000000000	00000000000000	0.00000	-0.000081	P
00000000000001	00000000000000	-0.00061	-0.000729	P
00000000000010	00000000000000	-0.00122	-0.001355	P
00000000000011	00000000000000	-0.00184	-0.001982	P
00000000000100	00000000000000	-0.00245	-0.00260	P
00000000001000	00000000000000	-0.00490 *	-0.005135	P
00000000010000	00000000000000	-0.00979 *	-0.010175	P
00000000100000	00000000000000	-0.01958 *	-0.020260	P
00000001000000	00000000000000	-0.03917 *	-0.040419	P
00000010000000	00000000000000	-0.07834 *	-0.080745	P
00000100000000	00000000000000	-0.15667 *	-0.16138	P
00001000000000	00000000000000	-0.31334 *	-0.32270	P
00010000000000	00000000000000	-0.62669 *	-0.64541	P
00100000000000	00000000000000	-1.25338 *	-1.2909	P
01000000000000	00000000000000	-2.50675 *	-2.5817	P
10000000000000	00000000000000	-5.01350 *	-5.1633	P

* Tolerance on output voltage is $\pm 10\%$

Step 2:

unturned
9-10-97
 ± 0.00015
 ± 0.00060
 ± 0.00030

Actual Position (API) MSB LSB	Command Position (CP) MSB LSB	ARI Output Voltage Required (Vdc)	Test Result (Vdc)	Pass/Fail
00000000000000	00000000000000	0.00000	-0.00007	P
00000000000000	00000000000001	0.00061	0.000541	P
00000000000000	00000000000010	0.00122	0.001180	P
00000000000000	00000000000011	0.00184	0.001794	P
00000000000000	00000000000100	0.00245	0.002440	P
00000000000000	00000000001000	0.00490 *	0.004969	P
00000000000000	00000000010000	0.00979 *	0.010036	P
00000000000000	00000000100000	0.01958 *	0.020110	P
00000000000000	00000001000000	0.03917 *	0.040281	P
00000000000000	00000010000000	0.07834 *	0.080590	P
00000000000000	00000100000000	0.15667 *	0.16131	P
00000000000000	00001000000000	0.31334 *	0.32269	P
00000000000000	00010000000000	0.62669 *	0.64551	P
00000000000000	00100000000000	1.25338 *	1.2908	P
00000000000000	01000000000000	2.50675 *	2.5816	P
00000000000000	10000000000000	-5.01350 *	-5.1633	P

* Tolerance on output voltage is $\pm 10\%$

19 Jun 97

TEST DATA SHEET B-13 (Sheet 3 of 3)

INTERFACE/CONVERTER CCA (P/N 1331697) (Paragraph 6.13.7)

6.13.7.5 Strobe FunctionStep 1: Strobe LowNo E11 Change
with Input CP ChangesPass/FailPStep 2: Strobe HighE11 Change
with Input CP ChangesPass/FailP6.13.7.6 Amplifier Gain

	<u>Measured Value (Vdc)</u>	<u>Limits (Vdc)</u>	<u>Pass/Fail</u>
E11	<u>0.32269</u>	-	<u>P</u>
E10	<u>3.5530</u>	-	<u>P</u>
E10 Voltage E11 Voltage	<u>11.0</u>	10.7 - 11.3	<u>11.0 P</u> plus

6.13.7.7 Ground Isolation

	<u>Measured Value (MΩ)</u>	<u>Limits (MΩ)</u>	<u>Pass/Fail</u>
Pin 91 to Pin 7 DC Resistance	<u>larger than 170MΩ</u>	>20	<u>P</u>

Comments:

NONE

Conducted by:

Dennis Lind
Test Engineer8/5/97

Date

Verified by:

Richard Stutts
Quality Control Inspector7A
190OCT 13 '97

Date

Approved by:

Dishon Thomas
DCMC10/14/97

Date

TEST DATA SHEET B-4 (Sheet 1 of 2)

MOTOR DRIVER 3-HALL SENSOR CCA (P/N 1331694) (Paragraph 6.4.3)

S/N: F08
Date: 4/21/97
1331694-4
6.4.3.2 Input Signal Offset

Step No.	Test Results	Limits
4	1.05 mV	0.0 ± 1 mVdc
6	1.35 mV	0.0 ± 1 mVdc
8	1.12 mV	0.0 ± 1 mVdc

Step No.	Test Resistor	Resistance Measured
13	E7-E8 (R25)	3.16K
	E9-E10 (R52)	4.48K
	E11-E12 (R33)	2.20K
	E13-E14 (R53)	4.24K
	E15-E16 (R42)	3.16K
	E17-E18 (R54)	4.52K

Step No.	Resistors	Selected Trim Resistors
14	R25	RNC55J3161FS
	R52	RNC55J4531FS
	R33	RNC55J2801FS
	R53	RNC55J4221FS
	R42	RNC55J3161FS
	R54	RNC55J4531FS

Step No.	E Point	Test Results	Limits	Pass/Fail
19	E19	+0.04 mV	0.0 ± 1 mVdc	P
	E20	+0.11 mV	0.0 ± 1 mVdc	P
	E21	+0.13 mV	0.0 ± 1 mVdc	P

6.4.3.3 Motor Driver Operation

Clockwise Rotation:

Step No.	Test Results	Limits	Pass/Fail
2	+5.00V	+5V±0.05Vdc	P
	49.1 mA	70mAdc max	P
	+15.07V	+15V±0.15Vdc	P
	1.5 mA	3.0mAdc max	P
	-14.98V	-15V±0.15Vdc	P
	18.6 mA	25mAdc max	P
	28.03V	+28V±0.5Vdc	P
	5.6 mA	8mAdc max	P
3	287 mV	400mVdc max	P
4	43.0 mA	50mAdc max	P
5	47.7 mA	50mAdc max	P

TEST DATA SHEET B-4 (Sheet 2 of 2)

MOTOR DRIVER 3-HALL SENSOR CCA (P/N 1331694) (Paragraph 6.4.3)

Counter Clockwise Rotation:

Step No.	Test Results	Limits	Pass/Fail
3	269 mV	400mVdc max	P
4	36.6 mA	50mAdc max	P
5	39.8 mA	50mAdc max	P

6.4.3.4 Current Limit Test

Step No.	Test Results	Limits	Pass/Fail
2	440 mA	350-500mAdc	P

Comments:

NONE

Conducted by:

Test Engineer

Date

Verified by:

Quality Control Inspector

Date

Approved by:

DCMC

Date

TEST DATA SHEET B-4 (Sheet 1 of 2)

MOTOR DRIVER 3-HALL SENSOR CCA (P/N 1331694) (Paragraph 6.4.3)

S/N: F07
Date: 4/21/97
1331694-4
6.4.3.2 Input Signal Offset

Step No.	Test Results	Limits
4	0.93 mV	0.0 ± 1 mVdc
6	0.92 mV	0.0 ± 1 mVdc
8	0.94 mV	0.0 ± 1 mVdc

Step No.	Test Resistor	Resistance Measured
13	E7-E8 (R25)	3.16 K
	E9-E10 (R52)	4.25 K
	E11-E12 (R33)	3.16 K
	E13-E14 (R53)	4.30 K
	E15-E16 (R42)	3.40 K
	E17-E18 (R54)	4.75 K

Step No.	Resistors	Selected Trim Resistors
14	R25	RNC55J3161FS
	R52	RNC55J4221FS
	R33	RNC55J3161FS
	R53	RNC55J4221FS
	R42	RNC55J3401FS
	R54	RNC55J4751FS

Step No.	E Point	Test Results	Limits	Pass/Fail
19	E19	- 0.02 mV	0.0 ± 1 mVdc	P
	E20	+ 0.02 mV	0.0 ± 1 mVdc	P
	E21	- 0.02 mV	0.0 ± 1 mVdc	P

6.4.3.3 Motor Driver Operation

Clockwise Rotation:

Step No.	Test Results	Limits	Pass/Fail
2	5.00V	+5V ± 0.05Vdc	P
	52.5 mA	70mA dc max	P
	+ 15.07V	+15V ± 0.15Vdc	P
	1.5 mA	3.0mA dc max	P
	- 14.98V	-15V ± 0.15Vdc	P
	13.7 mA	25mA dc max	P
	28.04V	+28V ± 0.5Vdc	P
	5.6 mA	8mA dc max	P
3	235 mV	400mVdc max	P
4	42.6 mA	50mA dc max	P
5	47.6 mA	50mA dc max	P

TEST DATA SHEET B-4 (Sheet 2 of 2)

MOTOR DRIVER 3-HALL SENSOR CCA (P/N 1331694) (Paragraph 6.4.3)

Counter Clockwise Rotation:

Step No.	Test Results	Limits	Pass/Fail
3	299mV	400mVdc max	P
4	37.1mA	50mAdc max	P
5	39.7mA	50mAdc max	P

6.4.3.4 Current Limit Test

Step No.	Test Results	Limits	Pass/Fail
2	440mA	350-500mAdc	P

Comments:

NONE

Conducted by:

Test Engineer

Date

Verified by:

Quality Control Inspector

Date

Approved by:

DCMC

Date

TEST DATA SHEET B-5 (Sheet 1 of 3)

R-D CONVERTER/OSCILLATOR CCA (P/N 1337739) (Paragraph 6.5.7)

Date 8/26/97
CCA S/N F12
1337739-2

6.5.7.1 UUT Pre-Test

Step 2:

Supply Currents (Without UUT)

Supply (Vdc)	(Baseline) Measured Value (mA) (Without UUT)	Limits (mA)	Pass/Fail
+15	0.06	0-1	P
-15	-0.28	-1 - 0	P
+5	0.06	0-1	P

Supply Voltages (Without UUT)

Supply	Measured Value (V)	Limits (V)	Pass/Fail
+15V (I)	15.02	± 0.50	P
-15V (I)	-15.01	± 0.50	P
+5V (I)	5.03	±0.25	P

Step 6:

Supply Currents (UUT Installed)

Supply (Vdc)	Measured Value (mA) (UUT Installed)	Difference (mA) (Measured - Baseline)	Limits (mA)	Pass/Fail
+15	27.02	26.96	20-40	P
-15	-36.27	-35.99	-30 - -50	P
+5	55.84	55.78	30-70	P

6.5.7.2 Supply Voltages (UUT Installed)

Supply	Measured Value (V)	Limits (V)	Pass/Fail
+15V (I)	15.01	± 0.50	P
-15V (I)	-14.97	± 0.50	P
+5V (I)	5.02	±0.25	P

6.5.7.3 Oscillator Frequency, Duty Cycle, and Output Voltage

Parameter	Measured Value	Limits	Pass/Fail
Frequency	1617 Hz	1550-1650 Hz	P
Duty Cycle	51.4 %	45-55 %	P
Output Voltage	7.86V	7.6-8.4 Vrms	P

TEST DATA SHEET B-5 (Sheet 2 of 3)

R-D CONVERTER/OSCILLATOR CCA (P/N 1337739) (Paragraph 6.5.7)

6.5.7.4 R-D Converter Operation

Step 1:

Bit Number/ Test Fixture Label	CW Pass/Fail	CCW Pass/Fail
API 0/1	P	P
API 1/2	P	P
API 2/3	P	P
API 3/4	P	P
API 4/5	P	P
API 5/6	P	P
API 6/7	P	P
API 7/8	P	P
API 8/9	P	P
API 9/10	P	P
API 10/11	P	P
API 11/12	P	P
API 12/13	P	P
API 13/14	P	P
Converter Busy	P	P

Step 2:

RS (E10)	Measured Value (Vdc)	Calculated Value (Vdc) * CCA -1 Assy	Calculated Value (Vdc) * CCA -2 Assy	Pass/Fail
CW Rotation**	1.627V	(+) N/A	(+) 1.790	P
CCW Rotation**	-1.757V	(-) N/A	(-) 1.790	P

* Signal level function of test and calibration gain resistors. Record calculated value and measured value. Measured value shall be within $\pm 10\%$ percent of calculated value. The equation is as follows:

$$V = \pm 0.155 \left(\frac{R_{20}}{R_{17}} \right) \pm 10\%$$

$$= 0.155 \left(\frac{59k}{5.11k} \right) = 1.790V$$

20
 226
 8-26-97
 20
 226
 8-26-97

6.5.7.5 Amplifier Gain

PES-RS	Measured Value (Vdc)	Limits (Vdc)	Pass/Fail
PES = +0.300 Vdc	1.091V	1.00 to 1.30	P
PES = -0.300 Vdc	1.164V	1.00 to 1.30	P

6.5.7.6 Direction Control Signal

DIR CNTRL	Measured Value (Vdc)	Limits (Vdc)	Pass/Fail
CW Rotation	5.000V	4.5 to 5.5	P
CCW Rotation	0.125V	0.0 to 0.4	P

TEST DATA SHEET B-5 (Sheet 3 of 3)

R-D CONVERTER/OSCILLATOR CCA (P/N 1337739) (Paragraph 6.5.7)

6.5.7.7 Notch Filter Frequency Response

Frequency	Measured Value (Hz)	Calculated Value (Hz) * CCA -1 Assy	Calculated Value (Hz) * CCA -2 Assy	Pass/Fail
AR3 Notch	N/A	N/A	N/A	N/A
AR4 Notch	↓	↓	↓	↓
AR5 Notch				

* Notch frequencies shall be within ± 3 percent of values determined by test and calibration resistors. Record calculated and measured values.

Comments:

NONE

Conducted by:

Dennis Lee
Test Engineer

8/26/97
Date

Verified by:

(7A) 268
Quality Control Inspector

NOV 19 '97
Date

Approved by:

(DCMC)
DCMC

11-19-97
Date

X=110.9ms ΔX=5.861 S
 Y=6.49054 ΔY=10.38 V

CAP TIM BUF

36.0

Diff = 10.38V

Voltage per degree = $10.38V \div 96.658^\circ = 0.1073889 V$


1% Motion = $0.1073889 \times 0.033333' / 1\% = 3.5795 mV$ (1% motion)

Jitter Limit = $\pm 5\% = \pm 5 \times 3.5795 mV = 17.8975 mV \Rightarrow 35.795 mV$ P-P

Overshoot Limit = $\pm 4\%$ above Upper Jitter Limit = $\pm 4 \times 35.795 mV = 14.318 mV$ (for a period of 19 msec.)
 $= 17.8975 mV + 14.318 mV = 32.2155 mV$ above mean value

Real

V



FxdY 0.0 Sec

7AP_FSS

8.0

SCAN MOTION AND JITTER

3.4.5.5

TEST ENG: *Ray [Signature]*

DATE: 6-15-99

QUALITY: *(67/88)*


PN: 1331200-2-JT SN: 109

B1

B1

X=163.3mS ΔX=38.67mS Y=6.84402 ΔY=17.45mV
 Yd=6.49054 ΔYd=353.6mV

CAP TIM BUF
 6.96



SO: 727181
 DATE: 6-15-99
 TEST ENG: *[Signature]*
 QUALITY: *[Signature]*
 SN: 109
 R2

X=366.0ms

Y=7.22696

$\Delta X = 39.84ms$


$\Delta Y = 18.23mV$

Y_a=6.84085

$\Delta Y_a = 363.3mV$

CAP TIM BUF

7.36



6.72

Exd X 364m

Sec BP-3

7AP_FSS

573m

SO: 727181

3.45.5 B3

TEST ENG: Ray

DATE: 6-15-99

PN: 1331200-2-IT SN: 109

QUALITY: B3

B3

$X=568.0ms$ $\Delta X=38.28ms$ $Y=7.61998$ $\Delta Y=18.23mV$
 $Y_a=7.2155$ $\Delta Y_a=384.4mV$

CAP TIM BUF
7.76

80.0 m
/Div

Real

7.12


Fxd X 568m

Sec

BP-4

7AP_FS5

777m



$V_p = V_{SC} + 0.5 = 18.23mV$
 $0.5 = V_p - V_{SC} = 18.23mV - 17.8975mV = 0.33mV$

Jitter = 14.35 mVpp

RISE TIME = 38.28 msec


SO: 727181

3.4.5.5 B4

TEST ENG: *Ray D. [Signature]* DATE: 6-15-99

B4

X=770.3mS ΔX=39.84mS Y=7.97498 ΔY=18.62mV
 Yd=7.60473 ΔYd=350.3mV



SO: 727181 DATE: 6-15-99
 QNT: 12312000 2.IT QNT: 100
 TEST ENG: *Ray H. H. H.*
 QUALITY: (V)

X=973.4ms
Yd=7.95829
 $\Delta X=40.23ms$
 $\Delta Yd=350.3mV$

CAP TIM BUF
8.4811

0 3 7
0 4 8
0 5 9

1000

2

407.

EXP X 0972M Sec RP-6 7AP_FFS 1.18


SO: 727181

3.4.5.5 B6

B6

TEST ENG: K
QUALITY: 268

DATE: 6-15-99



1.18

X=1.177 S ΔX=38.28mS Y=8.68412 ΔY=17.84mV
Y=8.30861 ΔY=355.2mV

CAP TIM BUF
8.88

80.0 mV
/Div

Real

V

8.24

Fxd X 1.18

Sec BP-7

7AP_F55

1.39

SO: 727181


PN: 1331200-2-IT

SN: 109

3.15.5

B7

TEST ENG: Ray Hershberg DATE: 6-15-99
QUALITY: (signature)



X=1.379 S ΔX=37.5ms Y=9.04213 ΔY=19.78mV
 YQ=8.66378 ΔYQ=353.6mV


CAP TIM BUF
 9.2

80.0 m
 /Div

Real

V

8.56



Fxd X 1.38 Sec BP-8 7AP_F55 1.59

SO: 727181

REL. 4004000 0 IT CM: 100

3.4.5.5. B8

TEST ENG:


Ray H. H. H.

QUALITY: (000)

DATE: 6/5-99

X=1.581 S ΔX=39.84ms Y=9.39627 ΔY=18.62mV
 Y=9.02058 ΔY=355.2mV

CAP TIM BUF
9.52



8.88 Fxd X 1.58 Sec BP-9 7AP_F55 1.79
 SO: 727181 TEST ENG: *Ray* DATE: 6-15-99
 PN: 1331200-2-IT SN: 109 QUALITY: *99%*
 3.4.5.5. B9

X=1.782 S ΔX=38.28ms Y=9.75243 ΔY=17.45mV
 Y=9.37576 ΔY=353.6mV

CAP TIM BUF
 9.92


80.0 m
 /Div

$$V_P = V_{SC} + 0.5 = 17.45mV$$

$$O.S. = V_P - V_{SC} = 17.45mV - 17.8975mV = \underline{\underline{0.0mV}}$$

$$L_{Titter} = \underline{\underline{13.57 mV p-p}}$$

$$RISETIME = \underline{\underline{38.28 msec}}$$



9.28

Fxd X 1.78 Sec BP-10 7AP_FFS5 1.99

SO: 727181

3455. B10

TEST ENG: *Ray [Signature]*
 QUALITY: *[Signature]*


DATE: 6-15-99

PN: 1331200-2-IT SN: 109

$X=1.986\text{ S}$ $\Delta X=37.5\text{mS}$ $Y=10.1036$ $\Delta Y=19.39\text{mV}$
 $Y_0=9.73743$ $\Delta Y_0=342.2\text{mV}$

CAP TIM BUF
10.3

100
m
Div



Real

V

9.5

Fxd X 1.98 Sec BP-11 7AP_FSS 2.2

SO: 727181

3.4.5.5. B11

TEST ENG: *Lay Thompson* DATE: 6-15-99
 QUALITY: *(signature)*

X=2.188 S ΔX=38.67ms Y=10.4421 ΔY=24.73mV
 Yd=10.0861 ΔYd=356.8mV


CAP TIM BUF
 10.7

100
 m
 /Div

Real

V

9.9



Fxd X 2.19 Sec BP-12

7AP_F55

2.4

SO: 727181

3.455. B12


TEST ENG: *Ray H. H. H.* DATE: 6-15-99

DN: 1331200.2.IT SN: 109

QUALITY:

X=2.389 S ΔX=39.06ms Y=10.8308 ΔY=27.15mV
 Yd=10.4381 ΔYd=366.5mV

CAP TIM BUF
 11.0



Fxd X 2.39 Sec BP-13 7AP_FSS 2.6

SO: 727181

3.4.5.5 B13

TEST ENG: *Ray Kershner* DATE: 6-15-99

ENL 4324200 9 IT CN: 100

X=2.593 S ΔX=35.55ms Y=11.1818 ΔY=22.79mV
 Yd=10.8013 ΔYd=353.6mV

CAP TIM BUF
 11.4

100
 m
 /Div

Real

V

10.6

Fxd X 2.59

Sec

BP-14

7AP_FS5

2.81


SO: 727181

3.4.55 B14

TEST ENG: *Lay* DATE: 6-15-99

QTY: 4000000

QTY: 400




X=2.796 S ΔX=38.28mS Y=11.5372 ΔY=22.79mV
 Yd=11.1598 ΔYd=353.6mV

CAP TIM BUF
 11.8

100
 F
 DIV

Real



11.0


Fxd X 2.79 Sec BP-15 7AP_FSS 3.01

SO: 727181 3.4.5.5 B15 TEST ENG: *Ray Campbell* DATE: 6-15-99
 DN: 123120002.IT SN: 109 QUALITY: (2/3)

X=2.998 S ΔX=37.89mS Y=11.8916 ΔY=21.33mV
 Y0=11.5117 ΔY0=356.8mV

CAP TIM BUF
 12.2

100
 m
 /Div



11.4

FXF X 2.99 Sec BP-16 7AP_F55

3.22

SO: 727181

PN: 1331200-2-IT

SN: 109

34.55

B16

TEST ENG:


Ray [Signature]

QUALITY: (8/4)

DATE: 6-15-99

X=3.201 S ΔX=37.5ms Y=12.2458 ΔY=20.36mV
 Yd=11.8653 ΔYd=360.0mV

CAP TIM BUF
 12.4




11.6

Exp X 3.19 Sec BP-17 7AP_F55 3.41
 SO: 727181 3.4.5.5. B17 TEST ENG: *Ray Hefley* DATE: 6-15-99
 DNI- 4324200.2JT SN: 100 QUALITY: (8.5)

X=3.404 S ΔX=36.33mS Y=12.6007 ΔY=24.73mV
 Y=12.2237 ΔY=351.9mV

CAP TIM BUF
 12.8

100
 m
 /Div



Exd X 3.4 Sec BP-18 7AP_FSS 3.62

SO: 727181

3.45.5- B18

TEST ENG:

Raymond

DATE: 6-15-99


QUALITY:

100

X=3.606 S ΔX=36.72ms Y=12.9348 ΔY=28.12mV
 Y0=12.574 ΔY0=361.7mV

CAP TIM BUF
 13.2

100
 m
 /Div



Real

V

12.4

Expd X 3.6

Sec

BP-19

7AP_FFS

3.82

SO: 727181

DN: 1331200-2JT

SN: 109

3.4.5.5 B19


TEST ENG:

Ray Anthony

QUALITY:

DATE: 6-15-99

$X=3.809\text{ S}$ $\Delta X=36.72\text{ms}$ $Y=13.3158$ $\Delta Y=23.76\text{mV}$
 $Y_0=12.9357$ $\Delta Y_0=356.8\text{mV}$



SO: 727181

3455. B20

TEST ENG:

DATE: 6-15-99


REL: 4334000 3 IT CNI: 400

(48)
 87
 Lay Thompson

X=4.214 S ΔX=33.98ms
Y=13.6574 ΔY=24.24mV

Y=14.0216 ΔY=24.24mV

CAP TIM BUF



Exp X 4.2 Sec BP-22 7 AP FS5 4.42

SO: 727181

PN: 1331200-2-IT SN: 109

3.7.5.5. B22

TEST ENG: Ray [Signature] DATE: 6/15/99

QUALITY: (8.7/8.8)

X=4.416 S ΔX=34.77ms Y=14.3784 ΔY=23.27mV
 Yc=13.9996 ΔYc=355.2mV


CAP TIM BUF
 14.6

100
 M
 /DIV

Real

V

13.8



Exp X 4.41 Sec BP-23 7AP_F55 4.63

SO: 727181

3.4.5.5. B23

TEST ENG: *Lay Huppert*
 QUALITY: *PS*

DATE: 6-15-99

X=4.617 S ΔX=36.72mS Y=14.7308 ΔY=23.27mV
 YQ=14.3548 ΔYQ=347.1mV


CAP TIM BUF
 14.9

100
 m
 /Div

Real

V

14.1



4.83

7AP_FFS5

Sec 8P-24

Fxd X 4.61

SO: 727181

3.45.5. B24

DATE: 8-15-99


TEST ENG: Ray Hestley
 QUALITY: (8.5)

DATE: 12/12/00 3 IT CNI: 100

X=4.821 S ΔX=37.89mS Y=15.0897 ΔY=24.73mV
 YQ=14.7083 ΔYQ=358.4mV

CAP TIM BUF
 15.4

100
 m
 /Div




14.6

FXD X 4.82 Sec BP-25 7AP_FSS 5.04
 SO: 727181 TEST ENG: *Raymond H. H.* DATE: 6-15-99
 PN: 1331200-2-IT SN: 109 QUALITY: *26%*

CAP TIM BUF
15.71

100 m
/DiV



14.

EXP	X 5.02	Sec	BP-26	7AP	FS5	5.24
-----	--------	-----	-------	-----	-----	------

SO: 727181

3455. B26


TEST ENG: Ray Bennett DATE: 6-15-89

6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525
 526
 527
 528
 529

X=5.227 S ΔX=36.33ms Y=15.8057 ΔY=28.12mV
 Yd=15.4171 ΔYd=360.0mV

CAP TIM BUF
 16.1

100
 m
 /Div



15.3

FXD X 5.23 Sec BP-27 7AP_FSS 5.44
 SO: 727181 3.7.55. B27 TEST ENG: *[Signature]* DATE: 6-15-99
 PN: 1331200-2-IT SN: 109 QUALITY: *[Signature]* 100%

$X=5.428\text{ S}$ $\Delta X=37.11\text{ mS}$ $Y=16.1576$ $\Delta Y=20.85\text{ mV}$
 $Y_0=15.7787$ $\Delta Y_0=353.6\text{ mV}$

CAP TIM BUF
16.4

100
m
/DIV

Reol

V

15.6

$$V_p = U_{SC} + OS = 20.85\text{ mV}$$

$$OS = V_p - U_{SC} = 20.85\text{ mV} - 17.8975\text{ mV} = \underline{2.95\text{ mV}}$$

13.28 mSec

MEAN VALUE

RISE TIME = 37.1 mSec

$L.T._{\text{Rev}} = 12.12\text{ mSec}$ $\left(\frac{13.28}{1.1}\right)$

5.64

7AP_FSS

Sec 8P-28

Fxd X 5.42

TEST ENG: *Ray Hensley* DATE: 6-15-99

3455. B28

SO: 727181


DN: 12212000.0.IT QN: 100

QUALITY: *(signature)*

X=5.629 S ΔX=36.72ms Y=16.528 ΔY=26.67mV
 Y0=16.1388 ΔY0=356.8mV

CAP TIM BUF
 16.8

100
 M
 /Div



16.0

Fxd X 5.63 Sec BP-29 7AP_F55 5.85

SO: 727181

PN: 1331200-2-IT

SN: 109


3.4.5.5. B29

TEST ENG:

QUALITY:

DATE: 6-15-99

X=5.832 S ΔX=38.28ms Y=16.8901 ΔY=21.82mV
 Y0=16.5004 ΔY0=368.2mV



Exp X 5.82 Sec BP-30 7AP_FSS 6.04
 SO: 727181 3455 B30 TEST ENG: *[Signature]* DATE: 6-15-99
 PN: 1331200-2-IT SN: 109 QUALITY: *[Signature]*

X=6.036 S ΔX=210.2ms Y=20.6429 ΔY=23.27mV
 Y0=16.8702 ΔY0=3.763 V

CAP TIM BUF
 22.4

800 m
 /Div

Reel

V

16.0

FXD X 6.04 Sec COLD CAL 7AP_FSS 8.67

SO: 727181


PN: 1231200 2 IT SN: 109

34.5.5. B31

TEST ENG:

QUALITY:

DATE: 6-15-99



8.67

7AP_FSS

Sec COLD CAL

FXD X 6.04

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m

/Div

Reel

V

16.0

800 m


/Div

Reel

V

X=6.648 S ΔX=400.4mS Y=31.0739 ΔY=29.09mV
 Yd=20.6393 ΔYd=10.44 V

CAP TIM BUF
 36.0



7.5

7 AP F55

WARM CAL

Sec

Fxd X 6.65

DATE: 6-15-99

TEST ENG: Ray [Signature]


3.4.5.5 B32

SO: 727181

Q11417000 3 IT CN: 100

Q11417000 3 IT

TEST DATA SHEET 7 (SHEET 1 OF 4)
3.4.5.5: METSAT Scan Motion and Jitter Test

Test Setup Verified: 

Signature

Shop Order No. 727181

Step No.	Description	Requirement	Test Result	Pass/Fail
7	--	Stepping Slewing <8 sec period per Figure 25	< 8 sec period	P
9	Scene 1-2 3.33° step	<42 msec rise time per Figure 26	< 38.67 msec	P
		< ±5% jitter per Figure 26	< 1.73%	P
		< +4% overshoot for 19 msec	< 0%	P
10	Scene 2-3 3.33° step	<42 msec rise time per Figure 26	< 39.84 msec	P
		< ±5% jitter per Figure 26	< 2.00%	P
		< +4% overshoot for 19 msec	< 0.09%	P
11	Scene 3-4 3.33° step	<42 msec rise time per Figure 26	< 38.28 msec	P
		< ±5% jitter per Figure 26	< 2.00%	P
		< +4% overshoot for 19 msec	< 0.09%	P
12	Scene 4-5 3.33° step	<42 msec rise time per Figure 26	< 39.84 msec	P
		< ±5% jitter per Figure 26	< 1.89%	P
		< +4% overshoot for 19 msec	< 0.20%	P
13	Scene 5-6 3.33° step	<42 msec rise time per Figure 26	< 40.23 msec	P
		< ±5% jitter per Figure 26	< 2.16%	P
		< +4% overshoot for 19 msec	< 0%	P
14	Scene 6-7 3.33° step	<42 msec rise time per Figure 26	< 38.28 msec	P
		< ±5% jitter per Figure 26	< 2.16%	P
		< +4% overshoot for 19 msec	< 0%	P
15	Scene 7-8 3.33° step	<42 msec rise time per Figure 26	< 37.5 msec	P
		< ±5% jitter per Figure 26	< 2.00%	P
		< +4% overshoot for 19 msec	< 0.52%	P
16	Scene 8-9 3.33° step	<42 msec rise time per Figure 26	< 39.84 msec	P
		< ±5% jitter per Figure 26	< 2.00%	P
		< +4% overshoot for 19 msec	< 0.20%	P

Pass = P
Fail = F

B33 a

TEST DATA SHEET 7 (SHEET 2 OF 4)
3.4.5.5: METSAT Scan Motion and Jitter Test

Step No.	Description	Requirement	Test Result	Pass/Fail
17	Scene 9-10 3.33° step	<42 msec rise time per Figure 26	< 38.28 msec	P
		< ±5% jitter per Figure 26	< 1.87%	P
		< +4% overshoot for 19 msec	< 0%	P
18	Scene 10-11 3.33° step	<42 msec rise time per Figure 26	< 37.5 msec	P
		< ±5% jitter per Figure 26	< 1.62%	P
		< +4% overshoot for 19 msec	< 0.42%	P
19	Scene 11-12 3.33° step	<42 msec rise time per Figure 26	< 38.67 msec	P
		< ±5% jitter per Figure 26	< 1.42%	P
		< +4% overshoot for 19 msec	< 1.70%	P
20	Scene 12-13 3.33° step	<42 msec rise time per Figure 26	< 39.06 msec	P
		< ±5% jitter per Figure 26	< 1.08%	P
		< +4% overshoot for 19 msec	< 2.58%	P
21	Scene 13-14 3.33° step	<42 msec rise time per Figure 26	< 35.55 msec	P
		< ±5% jitter per Figure 26	< 1.62%	P
		< +4% overshoot for 19 msec	< 1.36%	P
22	Scene 14-15 3.33° step	<42 msec rise time per Figure 26	< 38.28 msec	P
		< ±5% jitter per Figure 26	139 T 1.96%	P
		< +4% overshoot for 19 msec	0.95% < 1.36%	P
23	Scene 15-16 3.33° step	<42 msec rise time per Figure 26	< 37.89 msec	P
		< ±5% jitter per Figure 26	< 1.87%	P
		< +4% overshoot for 19 msec	< 0.95%	P
24	Scene 16-17 3.33° step	<42 msec rise time per Figure 26	< 37.5 msec	P
		< ±5% jitter per Figure 26	< 2.03%	P
		< +4% overshoot for 19 msec	< 0.68%	P

Pass = P
Fail = F

B33 b

TEST DATA SHEET 7 (SHEET 3 OF 4)
3.4.5.5: METSAT Scan Motion and Jitter Test

Step No.	Description	Requirement	Test Result	Pass/Fail
25	Scene 17-18 3.33° step	<42 msec rise time per Figure 26	< 36.33 msec	P
		< ±5% jitter per Figure 26	< 1.82% ^{1.25}	P
		< +4% overshoot for 19 msec	< 1.90%	P
26	Scene 18-19 3.33° step	<42 msec rise time per Figure 26	< 36.72 msec	P
		< ±5% jitter per Figure 26	< 1.21%	P
		< +4% overshoot for 19 msec	< 2.85%	P
27	Scene 19-20 3.33° step	<42 msec rise time per Figure 26	< 36.72 msec	P
		< ±5% jitter per Figure 26	< 2.30%	P
		< +4% overshoot for 19 msec	< 1.63%	P
28	Scene 20-21 3.33° step	<42 msec rise time per Figure 26	< 39.06 msec	P
		< ±5% jitter per Figure 26	< 1.76%	P
		< +4% overshoot for 19 msec	< 2.04%	P
29	Scene 21-22 3.33° step	<42 msec rise time per Figure 26	< 33.98 msec	P
		< ±5% jitter per Figure 26	< 0.88%	P
		< +4% overshoot for 19 msec	< 1.77%	P
30	Scene 22-23 3.33° step	<42 msec rise time per Figure 26	< 34.77 msec	P
		< ±5% jitter per Figure 26	< 1.42%	P
		< +4% overshoot for 19 msec	< 1.50%	P
31	Scene 23-24 3.33° step	<42 msec rise time per Figure 26	< 36.72 msec	P
		< ±5% jitter per Figure 26	< 1.82%	P
		< +4% overshoot for 19 msec	< 1.50%	P
32	Scene 24-25 3.33° step	<42 msec rise time per Figure 26	< 37.89 msec	P
		< ±5% jitter per Figure 26	< 2.09%	P
		< +4% overshoot for 19 msec	< 1.90%	P

Pass = P
Fail = F

B33 c

TEST DATA SHEET 7 (SHEET 4 OF 4)
3.4.5.5: METSAT Scan Motion and Jitter Test

Step No.	Description	Requirement	Test Result	Pass/Fail
33	Scene 25-26 3.33° step	<42 msec rise time per Figure 26	< 34.37 msec	P
		< ±5% jitter per Figure 26	< 1.65% ¹³⁹ ₇	P
		< +4% overshoot for 19 msec	< 2.18%	P
34	Scene 26-27 3.33° step	<42 msec rise time per Figure 26	< 36.33 msec	P
		< ±5% jitter per Figure 26	< 1.42%	P
		< +4% overshoot for 19 msec	< 2.85%	P
35	Scene 27-28 3.33° step	<42 msec rise time per Figure 26	< 37.11 msec	P
		< ±5% jitter per Figure 26	< 1.65%	P
		< +4% overshoot for 19 msec	< 0.82%	P
36	Scene 28-29 3.33° step	<42 msec rise time per Figure 26	< 36.72 msec	P
		< ±5% jitter per Figure 26	< 2.25%	P
		< +4% overshoot for 19 msec	< 2.45%	P
37	Scene 29-30 3.33° step	<42 msec rise time per Figure 26	< 38.28 msec	P
		< ±5% jitter per Figure 26	< 1.65%	P
		< +4% overshoot for 19 msec	< 1.09%	P
38	Scene 30- Cold Cal 35.0° slew	<0.21 sec slew time per Figure 29	¹³⁹ ₁₂ 0.108° _{0.21 sec}	P
		< ±5% jitter per Figure 30	< ±0.108°	P
39	Cold Cal - Warm Cal 96.67° slew	<0.40 sec slew time per Figure 31	¹³⁹ ₇₂ 0.134° _{0.40 sec}	P
		< ±5% jitter per Figure 32	< ±0.134°	P

Pass = P
Fail = F

Unit: 1331200-2-1T

Serial No.: 109

Date: 6-15-99

Test Engineer: *Ray Hurlberg*

Quality Assurance: *[Signature]*

Customer Representative: *[Signature]*


6-17-99

B33d

X=4.769 S ΔX=165.2ms
Y=-1.9152m ΔY=206.2μV

Y=-303.03μ ΔY=39.95mV

CAP TIM BUF



Real

V

500ms/10mV

-10.0 mV
Exp Y 0.0

4 PLB-C
8.0 Sec SCAN
34.5.6. C1

Sec

8.0

SO: 727181

TEST ENG: Ray Hering DATE: 6-15-99

PN: 1331200-2-JT SN: 109

QUALITY: (34)

TEST DATA SHEET 8
3.4.5.6: METSAT Pulse Load Bus Current

Test Setup Verified: *Ray Berthling*
Signature

Shop Order No. 727181

3.4.5.6: 28V Bus Peak Current and Rise Time Test

Step No.	Requirement	Test Result	Pass/Fail
4	< 2 A peak any place in the scan	1.997 A	P
5	> 70 μ sec rise time, 3.33° step	2.344 msec	P
6	> 70 μ sec rise time, start of WC slew	3.906 msec	P
6	> 70 μ sec rise time, end of WC slew	1.953 msec	P

Pass = P
Fail = F

Unit: 1331200-2-1T

Serial No.: 109

Test Engineer: *Ray Berthling*

Quality Assurance: *TP 268*

Date: 6-15-99

JUN 16 '99

X=44.82 Hz
Yc=-15.283 dB

M: FREQ RESP
10.0

dB

Gain Margin = 15.283 dB

-90.0

FxdXY 5 Log Hz
Yb=-180.07 Deg

M: FREQ RESP
90.0

Phase

Deg

-720

FxdXY 5 Log Hz

SO: 727181



Gain Phase Margin

PN: 1331200-2-IT

SN: 109

π 3.458

D1a



TEST ENG: D. Lind DATE: 6/16/99

QUALITY: 2.74 JUN 17 99

X=10.97 Hz

Yd=-17.13m dB

I-M: FREQ RESP

10.0

dB

-90.0

FxdXY 5 Log Hz

Yb=-113.09 Deg

I-M: FREQ RESP

90.0

Phase

Deg

-720

FxdXY 5 Log Hz

SO: 727181

PN: 1331200-2-IT SN: 109

Gain Phase Margin

TP 3.4.5.8


D1b

TEST ENG: *D. Ford*


DATE: 6/16/99

QUALITY *(3.7)*

JUN 17 1999



Phase Margin = 180.00 - 113.09 = 66.91 deg.



X=44.82 Hz
Y=-15.249 dB

M: FREQ RESP
10.0

dB

Gain Margin = 15.249 dB

-90.0

FxdXY 5 Log Hz
Yb=-180.47 Deg
M: FREQ RESP
90.0

12GP_21

5k

Phase

Deg

-720

FxdXY 5 Log Hz

12GP_21

5k

SO: 727181

PN: 1331200-2-IT SN: 109

Gain Phase Margin TEST ENG: *D. L. L.* DATE: 6/6/99

IF 3.45.8

QUALITY: $\frac{89.2}{100}$ JUN 17 99


12GP-BP21

D2a

X=10.97 Hz
Y=-33.873m dB

M: FREQ RESP
10.0

dB



-90.0

FxdXY 5 Log Hz

YD=-113.2 Deg

M: FREQ RESP
90.0


Phase Margin = $180.0 - 113.2 = 66.8$ deg

Phase

Deg

-720

FxdXY 5 Log Hz



SO: 727181

Gain Phase Margin

TEST ENG: *D. Lind*

DATE: 6/16/97

PN: 1331200-2-IT

SN: 109

IP 3.45.8
12GP_BP21

D26

QUALITY: *(892)* JUN 17 '97

X=44.82 HZ
Y=-15.34 dB

M: FREQ RESP
10.0

dB

Gain Margin = 15.34 dB

-90.0

Fx dX Y 5 Log Hz

Yb=-180.8 Deg

M: FREQ RESP

90.0

Phase

Deg

-720

Fx dX Y 5 Log Hz

SO: 727181

PN: 1331200-2-IT

SN: 109

Gain Phase Margin


IP 3.45, 8
12GP-BP31

D3a

TEST ENG: D. Ford

QUALITY: (85%) JUN 17 '99

DATE: 6/14/99



X=10.876 Hz
Ya=8.92885m dB

M: FREQ RESP
10.0

dB

-90.0

FxdXY 5 Log Hz
Yb=-112.99 Deg
M: FREQ RESP
90.0

Phase

Deg

-720

FxdXY 5 Log Hz

SO: 727181

PN: 1331200-2-IT

SN: 109

Gain Phase Margin

MP 34.5.8
12GP_BP31

D36

TEST ENG: *W. J. Ford*

QUALITY: *4.5*

DATE: 6/16/99

12GP_31 5K

12GP_31

Phase Margin = $180.00 - 112.99 = 67.01$ deg

TEST DATA SHEET 9
3.4.5.8: METSAT Gain/Phase Margin Test

Test Setup Verified: Ray Hestberg

Signature

Shop Order No. 727181

3.4.5.8 Step 12: Gain/Phase Margin Test

Requirement	Test Result		Pass/Fail
12 dB minimum	1	15.283 dB	P
	2	15.249 dB	P
	3	15.344 dB	P
25 degrees minimum	1	66.91 deg.	P
	2	66.8 deg	P
	3	67.01 deg	P

Pass = P
Fail = F

Unit: 133/200-2-1T

Serial No.: 109

Date: 6-16-99

Test Engineer: Ray Hestberg

Quality Assurance: 7A 268 JUN 17 99

Customer Representative: 6-17-99

X=78.52 Hz
Y=-25.534 dBVrms

POWER SPEC2
10.0

10.0

/Div

dB

rms
V2

-70.0

FxdXY 100m Hz

OPERATIONAL GAIN MARGIN
3.45.9

SO: 727181

PN: 1331200-2-IT

SN: 109

3Avg 0%OVLP Unif

$R_{pot} = 52.47k\Omega$

$R_{58} = 26.1k\Omega$

GAIN MARGIN = 9.14dB

78.52 Hz

120F_PSI


312

TEST ENG: Ray Buckley DATE: 6-16-99

QUALITY: 99%

E1

TEST DATA SHEET 10
3.4.5.9: METSAT Operational Gain Margin Test

Test Setup Verified: 

Signature

Shop Order No. 727181

3.4.5.9: Operation Gain Margin Test


Step No.	Requirement	Test Result		Pass/Fail
11	R58 Resistance (Kohms)		26.1K	P
	Test Pot Resistance (Kohms)	1	52.47K	
		2	52.43K	
12	Oscillation Frequency (Hz)	3	52.59K	P
		1	78.52 Hz	
		2	78.52 Hz	
16	Gain Margin, 9 dB minimum	3	78.52 Hz	P
		1	9.14 dB	
		2	9.14 dB	
		3	9.16 dB	

Pass = P
Fail = F


Unit: 1331200-2-1T

Serial No.: 109

Test Engineer: 

Quality Assurance: 

Date: 6-16-99

 National Aeronautics and Space Administration		Report Documentation Page	
1. Report No. ---	2. Government Accession No. ---	3. Recipient's Catalog No. ---	
4. Title and Subtitle Integrated Advanced Microwave Sounding Unit-A (AMSU-A), Performance Verification Report		5. Report Date 22 July 1999	
		6. Performing Organization Code ---	
7. Author(s) C. Haapala		8. Performing Organization Report No. 11528	
		10. Work Unit No. ---	
9. Performing Organization Name and Address Aerojet 1100 W. Hollyvale Azusa, CA 91702		11. Contract or Grant No. NAS 5-32314	
		13. Type of Report and Period Covered Final	
12. Sponsoring Agency Name and Address NASA Goddard Space Flight Center Greenbelt, Maryland 20771		14. Sponsoring Agency Code ---	
15. Supplementary Notes ---			
16. ABSTRACT (Maximum 200 words) This is the Performance Verification Report, Antenna Drive Subassembly, METSAT AMSU-A2 (P/N 1331200-2, S/N 109), for the Integrated Advanced Microwave Sounding Unit-A (AMSU-A).			
17. Key Words (Suggested by Author(s)) EOS Microwave System		18. Distribution Statement Unclassified --- Unlimited	
19. Security Classif. (of this report) Unclassified	20. Security Classif. (of this page) Unclassified	21. No. of pages	22. Price ---

NASA FORM 1626 OCT 86

PREPARATION OF THE REPORT DOCUMENTATION PAGE

The last page of a report facing the third cover is the Report Documentation Page, RDP. Information presented on this page is used in announcing and cataloging reports as well as preparing the cover and title page. Thus, it is important that the information be correct. Instructions for filling in each block of the form are as follows:

Block 1. Report No. NASA report series number, if preassigned.

Block 2. Government Accession No. Leave blank.

Block 3. Recipient's Catalog No. Reserved for use by each report recipient.

Block 4. Title and Subtitle. Typed in caps and lower case with dash or period separating subtitle from title.

Block 5. Report Date. Approximate month and year the report will be published.

Block 6. Performing Organization Code . Leave blank.

Block 7. Authors. Provide full names exactly as they are to appear on the title page. If applicable, the word editor should follow a name.

Block 8. Performing Organization Report No. NASA installation report control number and, if desired, the non-NASA performing organization report control number.

Block 9. Performing Organization Name and Address. Provide affiliation (NASA program office, NASA installation, or contractor name) of authors.

Block 10. Work Unit No. Provide Research and Technology Objectives and Plants (RTOP) number.

Block 11. Contract or Grant No. Provide when applicable.

Block 12. Sponsoring Agency Name and Address. National Aeronautics and Space Administration, Washington, D.C. 20546-0001. If contractor report, add NASA installation or HQ program office.

Block 13. Type of Report and Period Covered. NASA formal report series; for Contractor Report also list type (interim, final) and period covered when applicable.

Block 14. Sponsoring Agency Code. Leave blank.

Block 15. Supplementary Notes. Information not included

elsewhere: affiliation of authors if additional space is required for Block 9, notice of work sponsored by another agency, monitor of contract, information about supplements (file, data tapes, etc.) meeting site and date for presented papers, journal to which an article has been submitted, note of a report made from a thesis, appendix by author other than shown in Block 7.

Block 16. Abstract. The abstract should be informative rather than descriptive and should state the objectives of the investigation, the methods employed (e.g., simulation, experiment, or remote sensing), the results obtained, and the conclusions reached.

Block 17. Key Words. Identifying words or phrases to be used in cataloging the report.

Block 18. Distribution Statement. Indicate whether report is available to public or not. If not to be controlled, use "Unclassified-Unlimited." If controlled availability is required, list the category approved on the Document Availability Authorization Form (see NHB 2200.2, Form FF427). Also specify subject category (see "Table of Contents" in a current issue of STAR) in which report is to be distributed.

Block 19. Security Classification (of the report). Self-explanatory.

Block 20. Security Classification (of this page). Self-explanatory.

Block 21. No. of Pages. Count front matter pages beginning with iii, text pages including internal blank pages, and the RDP, but not the title page or the back of the title page.

Block 22. Price Code. If Block 18 shows "Unclassified-Unlimited," provide the NTIS price code (see "NTIS Price Schedules" in a current issue of STAR) and at the bottom of the form add either "For sale by the National Technical Information Service, Springfield, VA 22161-2171" or "For sale by the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402-0001," whichever is appropriate.

REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.				
1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE		3. REPORT TYPE AND DATES COVERED
4. TITLE AND SUBTITLE Integrated Advanced Microwave Sounding Unit-A (AMSU-A), Performance Verification Report			5. FUNDING NUMBERS NAS 5-32314	
6. AUTHOR(S) C. Haapala				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Aerojet 1100 W. Hollyvale Azusa, CA 91702			8. PERFORMING ORGANIZATION REPORT NUMBER 11528 22 July 1999	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) NASA Goddard Space Flight Center Greenbelt, Maryland 20771			10. SPONSORING/MONITORING AGENCY REPORT NUMBER ---	
11. SUPPLEMENTARY NOTES ---				
12a. DISTRIBUTION/AVAILABILITY STATEMENT ---			12b. DISTRIBUTION CODE ---	
13. ABSTRACT (Maximum 200 words) This is the Performance Verification Report, Antenna Drive Subassembly, METSAT AMSU-A2 (P/N 1331200-2, S/N 109), for the Integrated Advanced Microwave Sounding Unit-A (AMSU-A).				
14. SUBJECT TERMS EOS Microwave System			15. NUMBER OF PAGES	
			16. PRICE CODE ---	
17. SECURITY CLASSIFICATION OF REPORT Unclassified	18. SECURITY CLASSIFICATION OF THIS PAGE Unclassified	19. SECURITY CLASSIFICATION OF ABSTRACT Unclassified	20. LIMITATION OF ABSTRACT SAR	

GENERAL INSTRUCTIONS FOR COMPLETING SF 298

The Report Documentation Page (RDP) is used in announcing and cataloging reports. It is important that this information be consistent with the rest of the report, particularly the cover and title page. Instructions for filling in each block of the form follow. It is important to stay within the lines to meet optical scanning requirements.

Block 1. Agency Use Only (Leave blank)

Block 2. Report Date. Full publication date including day, month, and year, if available (e.g., 1 Jan 88). Must cite at least the year.

Block 3. Type of Report and Dates Covered. State whether report is interim, final, etc. If applicable, enter inclusive report dates (e.g., 10 Jun 87 - 30 Jun 88).

Block 4. Title and Subtitle. A title is taken from the part of the report that provides the most meaningful and complete information. When a report is prepared in more than one volume report the primary title, add volume number and include subtitle for the specific volume. On classified documents enter the title classification in parentheses.

Block 5. Funding Numbers. To include contract and grant numbers; may include program element number(s), project number(s), task number(s), and work unit number(s). Use the following labels:

C	-	Contract	PR	-	Project
G	-	Grant	TA	-	Task
PE	-	Program Element	WU	-	Work Unit Accession No.

Block 6. Author(s). Name(s) of person(s) responsible for writing the report, performing the research, or credited with the content of the report. If editor or compiler, this should follow the name(s).

Block 7. Performing Organization Name(s) and Address(es). Self-explanatory.

Block 8. Performing Organization Report Number. Enter the unique alphanumeric report number(s) assigned by the organization performing the report.

Block 9. Sponsoring/Monitoring Agency Name(s) and Address(es). Self-explanatory.

Block 10. Sponsoring/Monitoring Agency Reports Number. (if known).

Block 11. Supplementary Notes. Enter information not included elsewhere such as: Prepared in cooperation with ...; Trans. of ...; To be published in ... When a report is revised, include a statement whether the new report supersedes or supplements the older report.

Block 12.a Distribution/Availability Statement. Denotes public availability or limitations. Cite any availability to the public. Enter additional limitations or special markings in all capitals (e.g., NOFORN, REL, ITAR).

DOD - See DoDD 5230.24 *Distribution Statement on Technical Documents*

DOE - See authorities.

NASA - See Handbook NHB 2200.2.

NTIS - Leave blank.

Block 12.b Distribution Code.

DOD - Leave blank.

DOE - Enter DOE distribution categories from the standard Distribution for Unclassified Scientific and Technical Reports.

NASA - Leave blank.

NTIS - Leave blank.

Block 13. Abstract. Include a brief *Maximum 200 words* factual summary of the most significant information contained in the report.

Block 14. Subject Terms. Keywords or phrases identifying major subjects in the report.

Block 15. Number of Pages. Enter the total number of pages.

Block 16. Price Code. Enter appropriate price code (7IS only).

Block 17 - 19. Security Classifications. Self-explanatory. Enter U.S. Security Classification in accordance with U.S. Security Regulations (i.e., UNCLASSIFIED). If form contains classified information, stamp classification on the top and bottom of the page.

Block 20. Limitation of Abstract. This block must be completed to assign a limitation to the abstract. Enter either UL (unlimited) or SAR (same as report). An entry in this block is necessary if the abstract is to be limited. If blank, the abstract is assumed to be unlimited.



DOCUMENT APPROVAL SHEET

TITLE Performance Verification Report Antenna Drive Subassembly, METSAT AMSU-A2 (P/N 1331210-2, S/N: 109)		DOCUMENT NO. Report 11528 22 July 1999	
INPUT FROM: C. Haapala	CDRL: 208	SPECIFICATION ENGINEER: N/A	DATE
CHECKED BY: N/A	DATE	JOB NUMBER: N/A	DATE
APPROVED SIGNATURES		DEPT. NO.	DATE
Product Team Leader (A. Nieto) <u><i>[Signature]</i></u>		8341	7/27/99
Systems Engineer (R. Platt) <u><i>[Signature]</i></u>		8341	7/27/99
Design Assurance (E. Lorenz) <u><i>[Signature]</i></u>		8331	7/27/99
Quality Assurance (R. Taylor) <u><i>[Signature]</i></u>		7831	7/27/99
PMO/Technical (P. Patel) <u><i>[Signature]</i></u>		8341	7/30/99
Released: Configuration Management (J. Cavanaugh) <u><i>[Signature]</i></u>		8361	8/2/99
By my signature, I certify the above document has been reviewed by me and concurs with the technical requirements related to my area of responsibility.			
(Data Center) <u>FINAL</u>			
Please return this sheet and the reproducible master to Jim Kirk (Bldg. 1/Dept. 8631), ext. 2081.			

